

SUMMIT PLUMBING & MECHANICAL

Domestic Water Repipe Proposal

Prepared for Bluewater Hotel & Conference Center

Proposal #2026-047

Prepared by: Dan Kowalski, Owner

Date: June 12, 2026

Valid through: July 31, 2026

1. PROJECT OVERVIEW

Bluewater Hotel & Conference Center has experienced recurring pinhole leaks in the original 1998 copper domestic water distribution system serving the east wing (floors 2–4, 48 guest rooms). Repair frequency has increased from two events in 2024 to seven events in the past twelve months, resulting in guest relocations, drywall repairs, and rising emergency service costs.

Summit Plumbing & Mechanical proposes a phased repipe of the east wing domestic water system using Type L copper mains and PEX-A branch distribution, executed floor-by-floor to keep the hotel operational throughout the project.

2. SCOPE OF WORK

- Replace approximately 1,850 linear feet of domestic hot, cold, and recirculation piping serving the east wing.
- Install new isolation valves at each floor and each guest-room group (12 zones total), allowing future repairs without wing-wide shutdowns.
- Replace the east wing recirculation pump and balancing valves.
- Re-insulate all new piping to current energy code.
- Open and patch access points in corridor ceilings and select room walls; paint-ready finish by our licensed drywall subcontractor.
- Pressure test and disinfect each zone prior to return to service.
- Provide as-built riser diagrams and a valve schedule at close-out.

Exclusions: Fixture replacement, water heater plant, fire protection piping, hazardous material abatement (none expected; pre-1990 materials not present), and finish painting.

3. PHASING & TIMELINE

PHASE	AREA	DURATION	ROOMS OFFLINE
Mobilization & materials	—	2 weeks	0
Phase 1	Floor 2 (rooms 201–216)	3 weeks	8 at a time
Phase 2	Floor 3 (rooms 301–316)	3 weeks	8 at a time
Phase 3	Floor 4 (rooms 401–416)	3 weeks	8 at a time
Close-out & documentation	—	1 week	0

Total project duration: approximately 12 weeks from notice to proceed. Work hours 8:00 AM – 4:30 PM, Monday–Friday. Water shutdowns limited to the active zone and announced 48 hours in advance.

4. INVESTMENT

ITEM	AMOUNT
Labor — licensed plumbers (2 crews)	\$96,400
Materials — copper mains, PEX-A, valves, insulation	\$61,250
Recirculation pump & balancing	\$8,300
Drywall access & patching (subcontracted)	\$14,800
Permits, testing & disinfection	\$4,950
Total investment	\$185,700

Payment schedule: 20% at mobilization, 25% at completion of each floor phase, 5% at close-out. Pricing is firm for work commencing on or before September 1, 2026.

5. ASSUMPTIONS

- Hotel provides access to guest rooms per the agreed phasing schedule.
- Existing shut-off valves at the mechanical room function adequately for tie-ins; allowance included for two valve replacements if required.
- No asbestos-containing materials are present in work areas.
- Corridor ceiling access panels may be reused where undamaged.
- Guest room finishes beyond paint-ready patching are handled by hotel staff or others.

6. WHY SUMMIT PLUMBING & MECHANICAL

- 22 years serving commercial and hospitality clients in the region.
- Completed occupied-building repipes for Cedar Ridge HOA (2024) and Sunrise Assisted Living (2025) — references available.
- Licensed, bonded, and insured; \$2M general liability, \$5M umbrella.
- Dedicated project foreman on site daily with weekly written progress reports.

7. NEXT STEPS

- Review this proposal and confirm the preferred start window.
- Sign and return the acceptance page, or contact us with questions.
- We will schedule a pre-construction walkthrough within 10 business days of acceptance.

We appreciate the opportunity to earn Bluewater's business and are happy to adjust phasing or scope to fit your operational needs.